

석면비산측정 결과보고서

- 2013년 염전생산시설(창고, 해주) 슬레이트 처리사업 -
(신안군 비금면 지당리 333-39)



한국안전환경컨설팅(주)

Korea Safety & Environment Consulting CO.,LTD

T. 062-511-5479 F. 062-511-5480

[별 첨1] 측정 위치도(측정 장소)

2013년 염전생산시설(창고, 해주) 슬레이트 처리사업(신안군 비금면 지당리 333-39)



표 례	*NO					
	시료채취	부지경계선	대상 건축물	위생설비	폐기물야적	

[별첨2] 측정 결과

측정위치		측정시간(분)	유량(l/min)	측정농도 [기준: 0.01개/ cm^3]	초과여부
*1	부지경계선1	10:30 ~ 14:40	9.95	불검출 [검출한계 0.002미만]	미만
*2	부지경계선2	10:33 ~ 14:43	9.95	불검출 [검출한계 0.002미만]	미만
*3	부지경계선3	10:35 ~ 14:45	9.93	불검출 [검출한계 0.002미만]	미만
*4	부지경계선4	10:38 ~ 14:48	9.94	불검출 [검출한계 0.002미만]	미만
*5	작업장주변	10:50 ~ 13:00	9.95	불검출 [검출한계 0.002미만]	미만
*6	위생설비입구	13:10 ~ 13:55	9.93	불검출 [검출한계 0.002미만]	미만
*7	폐기물야적	14:00 ~ 14:45	9.94	0.002	미만

[별첨3] 측정 사진

측정 사진			
			
*1. 부지경계선1	*2. 부지경계선2	*3. 부지경계선3	*4. 부지경계선4
			
*5. 작업장주변	*6. 위생설비 입구	*7. 폐기물야적	